



खडक नगरपालिका  
नगर कार्यपालिकाको कार्यालय  
कल्याणपुर, सप्तरी  
प्रदेश नं. २, नेपाल  
कार्यालय कोड नं.: ८०१०२१५०२



*(Handwritten signature)*

### Bill of quantities (BoQ)

कार्यालय वा परियोजनाको नाम: जागेश्वर साहको घर देखि मनोज साहको घर सम्म आर.सि.सि. ढलान  
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल: खडक न.पा.वार्ड नं.-११

आर्थिक वर्ष: २०८२/०८३

| S.N. | Description of work  | Unit | Quantity | Rate (NRs) |          | Total Amount NRs. | Remarks |
|------|--|------|----------|------------|----------|-------------------|---------|
|      |  |      |          | In Figures | In Words |                   |         |
| 1    | Supplying of Information Board   | job  | 1.00     |            |          |                   |         |
| 2    | Photography work before and after construction of project  | job  | 1.00     |            |          |                   |         |
| 3    | Clearing grass/top soil and removal upto a distance of 50 meters outside the periphery of the area, including cutting and filling of small undulation by manual means.   | sqm. | 81.00    |            |          |                   |         |
| 4    | Roadway Excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer by Mechanical means(JCB). | cum. | 46.58    |            |          |                   |         |
| 5    | Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications By Mechanical means.  | cum. | 35.44    |            |          |                   |         |
| 6    | Providing and laying of Plain/ Reinforced Cement Concrete M20 (1:1.5:3 for nominal mix) in Foundations as per drawing and technical specifications.  | cum  | 35.44    |            |          |                   |         |

|   |  |      |                         |  |  |  |  |
|---|--|------|-------------------------|--|--|--|--|
| 7 | Providing and Laying, fitting and placing un-coated mild-steel/ HYSD reinforcement complete in foundation as per drawing and technical specification.                                    | Kg   | 1709.93                 |  |  |  |  |
| 8 | Providing, Preparing & Installing formwork including necessary supports and removing after completion for walls, (Class F2 finish) Vertical plain surface using soft wood height upto 3m | sqm. | 21.83                   |  |  |  |  |
| 9 | Lab Test( as per instruction of engineer )   | job  | 1.00                    |  |  |  |  |
|   |  |      | Total Amount NRs.       |  |  |  |  |
|   |  |      | 13 % VAT                |  |  |  |  |
|   |  |      | 3% Contengencis NRs.    |  |  |  |  |
|   |  |      | Grand Total Amount NRs. |  |  |  |  |

Net Total Amount in Words:-

Contractors Name:-

PAN/VAT no:-

Address:-

Signature:-

Stamp

Date:-

Authorised Name:-

